

I-40/CC ON RAMP

Maxxwell Townsend, Mohammed Alshaiban,
Zach Johnson, Ramon Lopez

CENE 476
December 6th, 2019

Project Purpose

- One Southbound entrance onto I-40 westbound
- Detention basin on north side
- Adding an additional right turn lane to the on ramp to increase capacity
- Expand existing on ramp from 1 to 2 lanes to reduce congestion



Figure 1-1: Zoomed in Project Location (Google Maps, NTS)

Stakeholders

- Arizona Department of Transportation
 - *Nate Reisner, P.E., Development Engineer*
- City of Flagstaff
 - *Daily users of this facility*



(Source: Wikipedia)

Project Location

- The On-Ramp is located on N Country Club Drive and is adjacent to Interstate 40 in Flagstaff, AZ




Figure 1-2: State of Arizona with Project Location (www.mapsoftheworld.com, 1" = 80 miles)



Figure 1-3: Zoomed in Project Location (Google Maps, NTS)

Task 1: Analyze/Review Existing Studies

- 1.1 Site Visit
- 1.2 Process Survey Data from GIS
- 1.3 Analyze Existing Drainage Studies/Obtain As-Built Information
- 1.4 Existing Runoff Calculations
- 1.5 Obtain and Analyze Geotechnical data from ADOT
- 1.6 Input and Process Existing Geometry into Civil 3D
- 1.7 Create Existing Cross Sections
- 1.8 Create Roadway Alignments/Base Files

Task 2: Design

- 2.1 Design/Create Proposed Cross-Sections
- 2.2 Initial Design
 - 2.2.1 Intersection Design
 - 2.2.2 On-Ramp Design
- 2.3 Final Design Geometry/Cross-Sections
- 2.4 Final Drainage Design
- 2.5 Stormwater Pollution Prevention Control Plan
- 2.6 Construction Plan Set
- 2.7 Synchro Analysis and Traffic Analysis Recommendation

Task 3 & 4: Deliverables and Project Impacts

- 3.1 30% Submittal (Task 1)
- 3.2 60% Submittal (Task 2)
- 3.3 90% Submittal (Tasks 2-4)
- 3.4 Final Design Concept Report Submittal (Tasks 2-4)
- 3.5 Website
- 4.1 Economic Impacts
- 4.2 Environmental Impacts
- 4.3 Social Impacts

Task 5: Project Management


- 5.1 Grading Instructor Meetings
- 5.2 Client Meetings
- 5.3 Technical Advisor Meetings
- 5.4 Team Meetings
- 5.5 Schedule Management
- 5.6 Cost/Resource Management

Exclusions

- Full Survey
- Geotechnical Analysis
- Collection of Traffic Data
- Traffic Signal Planning
- Environmental Permits / Mitigation Measures
- Bridge Design
- New Drainage Infrastructure Design

Task Name	Duration	Start	Finish
10/13/16/19/22/25/28/31/3/6/9/12/15/18/21/24/27/1/4/7/10/13/16/19/22/25/28/31/3/6/9/12/	20	February 2020	March 2020
			April 2020

1	Task 1: Existing Studies	16 days	Mon 1/13/20	Mon 2/3/20
2	1.1: Site Visit	1 day	Mon 1/13/20	Mon 1/13/20
3	1.2: Process Street Data from GIS	7 days	Tue 1/14/20	Wed 1/22/20
4	1.3: Studying Existing Drainage Studies/As-Built Information	3 days	Tue 1/14/20	Thu 1/16/20
5	1.4: Runoff Calculation	4 days	Tue 1/14/20	Fri 1/17/20
6	1.5: Analyze Existing Geotechnical Information	3 days	Tue 1/14/20	Thu 1/16/20
7	1.6: Input and Process Existing Geometry into Civil3D	5 days	Thu 1/23/20	Wed 1/29/20
8	1.7: Create Existing Cross-Sections	3 days	Thu 1/23/20	Mon 1/27/20
9	1.8: Create Roadway Alignments Base Files	3 days	Thu 1/30/20	Mon 2/3/20
10	Task 2: Design	56 days	Tue 1/28/20	Mon 4/20/20
11	2.1: Create Proposed Cross-Sections	4 days	Tue 1/28/20	Fri 1/31/20
12	2.2: Initial Design	27 days	Mon 2/3/20	Tue 3/10/20
13	2.2.1: Intersection Design	27 days	Mon 2/3/20	Tue 3/10/20
14	2.2.1: On-Ramp Design	27 days	Mon 2/3/20	Tue 3/10/20
15	2.3: Final Design Geometry/Cross-Sections	12 days	Thu 3/12/20	Thu 4/2/20
16	2.4: Final Drainage Design	12 days	Fri 4/3/20	Mon 4/20/20
17	2.5: Stormwater Pollution Prevention Control Plan	4 days	Fri 4/3/20	Wed 4/8/20
18	2.6: Construction Plan Set	50 days	Mon 2/3/20	Thu 4/16/20
19	2.7: Synchro Analysis and Traffic Analysis Recommendation	2 days	Wed 3/11/20	Thu 3/12/20
20	Task 3: Deliverables	47 days	Fri 2/14/20	Fri 4/24/20
21	3.1: 30% Submittal	1 day	Fri 2/14/20	Fri 2/14/20
22	3.2: 60% Submittal	1 day	Tue 3/10/20	Tue 3/10/20
23	3.3: 90% Submittal	1 day	Tue 4/21/20	Tue 4/21/20
24	3.4: Final Design Report	1 day	Fri 4/24/20	Fri 4/24/20
25	Task 4: Impacts	2 days	Fri 4/3/20	Mon 4/6/20
26	4.1: Social Impacts Assessment	2 days	Fri 4/3/20	Mon 4/6/20
27	4.2: Economic Impacts Assessment	2 days	Fri 4/3/20	Mon 4/6/20
28	4.3: Environmental Impacts Assessment	2 days	Fri 4/3/20	Mon 4/6/20
29	Task 5: Project Management	70.5 days	Mon 12/16/1	Thu 4/23/20



Staffing

- **612** Total estimated hours for this project
- PE will lead Design Work
- PM will review work and ensure QA/QC

Tasks	PM	PE	EIT	TECH	Total
2.1 Task 1: Existing Studies	6	18	40	52	116
2.2 Task 2: Design	17	38	98	74	227
2.3 Task 3: Deliverables	9	16	42	30	97
2.4 Task 4: Impacts	3	3	6	0	12
2.5 Task 5 Project Management	42	42	38	38	160
Total	77	117	224	194	612

Cost Estimate

- Total Estimated Cost of Engineering Services is **\$72,369**
- Travel Cost is Minimal, but was Included for Accuracy

1.0 Team Members	Billing Rate	Hours	Cost
PM	\$195.00	77	\$15,015.00
PE	\$155.00	117	\$18,135.00
EIT	\$110.00	224	\$24,640.00
TECH	\$75.00	194	\$14,550.00
Total			\$72,340.00
2.0 Travel			
8 Meetings @ 4 mi/meeting	\$0.58 mi/meeting		19
5 Meetings @ 2.5 mi/meeting	\$0.58 mi/meeting		10
Total			29
Total Cost of Engineering Services			\$72,369.00

References

- [1] “AASHTO-Roadside-Design-Guidelines,” American Association of State Highway and Transportation Officials, vol. 4th, 2011
- [2] “ADOT Roadway Design Guidelines,” *Arizona Department of Transportation*, May 2012
- [3] “Coconino County Map” (2016). [Image] Available at: www.mapsoftheworld.com [Accessed 4 Dec. 2019].

Questions?